

LATITUDE 47°28'11" LONGITUDE 122°57'27" T23N-R2W-20
TAHOYA RIVER BASIN

PHYSICAL DATA

DRAINAGE AREA 0.18 SQ MI
ALTITUDE 38. FT
LAKE AREA 28. ACRES
LAKE VOLUME 310. ACPE-FT
MEAN DEPTH 11. FT
MAXIMUM DEPTH 20. FT
SHORELINE LENGTH 1.1 MI
SHORELINE CONFIGURATION 1.4
DEVELOPMENT OF VOLUME 0.56
BOTTOM SLOPE 1.6 %
BASIN GEOLOGY SED./META.
INFLOW NONE VISIBLE
OUTFLOW CHANNEL PRESENT

CULTURAL DATA

RESIDENTIAL DEVELOPMENT 6 %
NUMBER OF NEARSHORE HOMES 2
LAND USE IN DRAINAGE BASIN
RESIDENTIAL URBAN 0 %
RESIDENTIAL SUBURBAN 0 %
AGRICULTURAL 0 %
FOREST OR UNPRODUCTIVE 76 %
LAKE SURFACE 24 %
PUBLIC BOAT ACCESS TO LAKE --

WATER-QUALITY DATA (IN MG/L UNLESS OTHERWISE INDICATED)

SAMPLE SITE


DATE 8/22/74
TIME 1040 1045
DEPTH (FT) 3. 13.
TOTAL NITRATE (N) 0.01 0.01
TOTAL NITRITE (N) 0.00 0.00
TOTAL AMMONIA (N) 0.08 0.07
TOTAL ORGANIC NITROGEN (N) 0.59 0.50
TOTAL PHOSPHORUS (P) 0.007 0.016
TOTAL ORTHOPHOSPHATE (P) 0.003 0.003
SPECIFIC CONDUCTANCE (MICROMHOS) 19 19
WATER TEMPERATURE (DEG C) 20.0 19.8
COLOR (PLATINUM-COBALT UNITS) 15 10
SECCHI-DISC VISIBILITY (FT) 9
DISSOLVED OXYGEN 8.2 7.9

LAKE SHORELINE COVERED BY EMERSED PLANTS 76-100 %
LAKE SURFACE COVERED BY EMERSED PLANTS NONE OR <1 %

DATE 8/22/74
TIME 1055
NUMBER OF FECAL COLIFORM SAMPLES 3
FECAL COLIFORM, MINIMUM (COL./100ML) <1
FECAL COLIFORM, MAXIMUM (COL./100ML) <1
FECAL COLIFORM, MEAN (COL./100ML) <1

REMARKS

THE LAKESHORE IS OCCUPIED BY A GIRL SCOUT CAMP. THE SHORELINE WAS COVERED BY A THIN MARGIN OF EMERSED PLANTS. THE LITTORAL BOTTOM IS MOSTLY SILT.



0 500 1000 FEET

EXPLANATION

— 10 —
Line of equal
water depth
Interval 5 feet

Bennetttsen Lake, Mason County. From Washington
Department of Game, March 1, 1951.



Bennetttsen Lake, Mason County. June 29, 1974. Approx. scale 1:4800.

RENSON LAKE

MASON COUNTY

LATITUDE 47*19'58" LONGITUDE 122*55'22" T21N-R2W-3
 PUGET SOUND BASIN

PHYSICAL DATA

 DRAINAGE AREA 0.63 SQ MI
 ALTITUDE 222. FT
 LAKE AREA 82. ACRES
 LAKE VOLUME 1900. ACRE-FT
 MEAN DEPTH 23. FT
 MAXIMUM DEPTH 35. FT
 SHORELINE LENGTH 1.7 MI
 SHORELINE CONFIGURATION 1.3
 DEVELOPMENT OF VOLUME 0.64
 BOTTOM SLOPE 1.6 %
 BASIN GEOLOGY SED./META.
 INFLOW NONE VISIBLE
 OUTFLOW CHANNEL PRESENT

CULTURAL DATA

 RESIDENTIAL DEVELOPMENT 95 %
 NUMBER OF NEARSHORE HOMES 93
 LAND USE IN DRAINAGE BASIN
 RESIDENTIAL URBAN 0 %
 RESIDENTIAL SUBURBAN 6 %
 AGRICULTURAL 0 %
 FOREST OR UNPRODUCTIVE 74 %
 LAKE SURFACE 20 %
 PUBLIC BOAT ACCESS TO LAKE YES

WATER-QUALITY DATA (IN MG/L UNLESS OTHERWISE INDICATED)


 SAMPLE SITE 1
 DATE 8/27/74
 TIME 1030 1035
 DEPTH (FT) 3. 28.
 TOTAL NITRATE (N) 0.00 0.00
 TOTAL NITRITE (N) 0.00 0.00
 TOTAL AMMONIA (N) 0.04 0.04
 TOTAL ORGANIC NITROGEN (N) 0.13 0.22
 TOTAL PHOSPHORUS (P) 0.008 0.008
 TOTAL ORTHOPHOSPHATE (P) 0.003 0.004
 SPECIFIC CONDUCTANCE (MICROMHOS) 18 18
 WATER TEMPERATURE (DEG C) 21.5 20.8
 COLOR (PLATINUM-COBALT UNITS) 0 0
 SECCHI-DISC VISIBILITY (FT) 15
 DISSOLVED OXYGEN 8.8 8.6

LAKE SHORELINE COVERED BY EMERSED PLANTS 1- 10 %
 LAKE SURFACE COVERED BY EMERSED PLANTS NONE OR <1 %

DATE 8/27/74
 TIME 1030
 NUMBER OF FECAL COLIFORM SAMPLES 4
 FECAL COLIFORM, MINIMUM (COL./100ML) <1
 FECAL COLIFORM, MAXIMUM (COL./100ML) 5
 FECAL COLIFORM, MEAN (COL./100ML) 2

REMARKS

 THE LAKE IS TIGHTLY SURROUNDED BY RESIDENTIAL HOMES. VERY FEW AQUATIC
 MACROPHYTES WERE SUPPORTED ON THE GRAVEL AND SAND LITTORAL BOTTOM.



N




0 1000 2000 FEET

EXPLANATION

— 10 —

Line of equal
water depth
Interval 5 feet

Benson Lake, Mason County. From Washington
Department of Game, August 5, 1951.



Benson Lake, Mason County. September 3, 1973. Approx. scale 1:12,000.

CRANBERRY LAKE

MASON COUNTY

LATITUDE 47°17' 4" LONGITUDE 123° 3'45" T21N-R3W-28
PUGET SOUND BASIN

PHYSICAL DATA

DRAINAGE AREA 9.03 SQ MI
ALTITUDE 230. FT
LAKE AREA 190. ACRES
LAKE VOLUME 890. ACRE-FT
MEAN DEPTH 5. FT
MAXIMUM DEPTH 10. FT
SHORELINE LENGTH 4.6 MI
SHORELINE CONFIGURATION 2.4
DEVELOPMENT OF VOLUME 0.46
BOTTOM SLOPE 0.31 %
BASIN GEOLOGY SED./META.
INFLOW INTERMITTENT
OUTFLOW CHANNEL PRESENT

CULTURAL DATA

RESIDENTIAL DEVELOPMENT 0 %
NUMBER OF NEARSHORE HOMES 0
LAND USE IN DRAINAGE BASIN
RESIDENTIAL URBAN 0 %
RESIDENTIAL SUBURBAN 0 %
AGRICULTURAL 0 %
FOREST OR UNPRODUCTIVE 97 %
LAKE SURFACE 3 %
PUBLIC BOAT ACCESS TO LAKE YES

WATER-QUALITY DATA (IN MG/L UNLESS OTHERWISE INDICATED)

SAMPLE SITE

DATE 8/16/74
TIME 1205 1210
DEPTH (FT) 3. 5.
TOTAL NITRATE (N) 0.02 0.01
TOTAL NITRITE (N) 0.00 0.00
TOTAL AMMONIA (N) 0.06 0.06
TOTAL ORGANIC NITROGEN (N) 0.71 0.69
TOTAL PHOSPHORUS (P) 0.023 0.020
TOTAL ORTHOPHOSPHATE (P) 0.004 0.004
SPECIFIC CONDUCTANCE (MICROMHOS) 59 59
WATER TEMPERATURE (DEG C) 19.1 19.1
COLOR (PLATINUM-COBALT UNITS) 10 10
SECCHI-DISC VISIBILITY (FT) > 7
DISSOLVED OXYGEN 10.6 10.6

LAKE SHORELINE COVERED BY EMERSED PLANTS 76-100 %
LAKE SURFACE COVERED BY EMERSED PLANTS 11- 25 %

DATE 8/16/74
TIME 1205
NUMBER OF FECAL COLIFORM SAMPLES 3
FECAL COLIFORM, MINIMUM (COL./100ML) <1
FECAL COLIFORM, MAXIMUM (COL./100ML) 5
FECAL COLIFORM, MEAN (COL./100ML) 2

REMARKS

A LARGE SHALLOW LAKE FED BY THREE UNNAMED TRIBUTARIES, ONE OF WHICH DRAINS A LARGE MARSH ON THE WEST SIDE OF THE LAKE. THE OUTFLOW IS VIA CRANBERRY CREEK WHICH FLOWS TO LIMERICK LAKE. AT ONE TIME THE LAKE WAS USED AS A SALMON REARING POND BY THE DEPT. OF FISHERIES. THE LAKE HAD A HEAVY COVER OF BOTH EMERSED AND SUBMERSED PLANTS. MOST OF THE EMERSED PLANTS ARE IN THE WEST BAY. THE LITTORAL BOTTOM IS SILT AND MUCK. THERE WERE LOGS AND WOOD DEBRIS ALONG THE SHORE.


N

0 1000 2000 FEET

EXPLANATION


— 4 —

Line of equal
water depth
Interval 2 feet



Cranberry Lake, Mason County.

From U.S. Geological Survey, February 4, 1974.



Cranberry Lake, Mason County. May 13, 1972. Approx. scale 1:12,000.

CUSHMAN LAKE

MASON COUNTY

LATITUDE 47°25' 9" LONGITUDE 123°13'25" T22N-R4W-5
SKOKOMISH RIVER BASIN

PHYSICAL DATA

DRAINAGE AREA 93.7 SQ MI
ALTITUDE 735. FT
LAKE AREA 4000. ACRES
LAKE VOLUME 450000. ACRE-FT
MEAN DEPTH 110. FT
MAXIMUM DEPTH 270. FT
SHORELINE LENGTH 23. MI
SHORELINE CONFIGURATION 2.6
DEVELOPMENT OF VOLUME 0.42
BOTTOM SLOPE 1.8 %
BASIN GEOLOGY IGNEOUS
INFLOW PERENNIAL
OUTFLOW CHANNEL PRESENT

CULTURAL DATA

RESIDENTIAL DEVELOPMENT 11 %
NUMBER OF NEARSHORE HOMES 62
LAND USE IN DRAINAGE BASIN
RESIDENTIAL URBAN 0 %
RESIDENTIAL SUBURBAN <1 %
AGRICULTURAL 0 %
FOREST OR UNPRODUCTIVE 93 %
LAKE SURFACE 7 %
PUBLIC BOAT ACCESS TO LAKE YES

WATER-QUALITY DATA (IN MG/L UNLESS OTHERWISE INDICATED)

SAMPLE SITE

	1		2		3	
	8/21/74		8/21/74		8/21/74	
DATE	1125	1130	1220	1225	1315	1320
TIME	3.	164.	3.	115.	3.	98.
DEPTH (FT)	0.02	0.07	0.04	0.02	0.02	0.02
TOTAL NITRATE (N)	0.00	0.00	0.00	0.00	0.00	0.00
TOTAL NITRITE (N)	0.02	0.02	0.02	0.02	0.02	0.05
TOTAL AMMONIA (N)	0.23	0.06	0.07	0.03	0.03	0.06
TOTAL ORGANIC NITROGEN (N)	0.004	0.002	0.004	0.001	0.002	0.001
TOTAL PHOSPHORUS (P)	0.002	0.002	0.002	0.001	0.001	0.001
TOTAL ORTHOPHOSPHATE (P)	55	60	56	60	56	60
SPECIFIC CONDUCTANCE (MICROMHOS)	18.6	5.9	19.0	7.1	19.2	8.3
WATER TEMPERATURE (DEG C)	0	0	0	0	0	0
COLOR (PLATINUM-COBALT UNITS)	25		25		26	
SECCHI-DISC VISIBILITY (FT)	9.1	9.8	9.0	9.6	8.9	9.7
DISSOLVED OXYGEN						

LAKE SHORELINE COVERED BY EMERSED PLANTS
LAKE SURFACE COVERED BY EMERSED PLANTS

LITTLE OR NONE
NONE OR <1 %

DATE 8/21/74
TIME 1030
NUMBER OF FECAL COLIFORM SAMPLES 7
FECAL COLIFORM, MINIMUM (COL./100ML) <1
FECAL COLIFORM, MAXIMUM (COL./100ML) 6
FECAL COLIFORM, MEAN (COL./100ML) 1

REMARKS

A NATURAL LAKE INCREASED IN SIZE BY A DAM ON THE NORTH FORK SKOKOMISH RIVER. THE LAKE IS USED FOR HYDROPOWER BY THE CITY OF TACOMA. THE UPPER PART OF THE DRAINAGE BASIN IS NATIONAL FOREST, BUT DEVELOPMENT IN THE FORM OF RECREATIONAL AND RESIDENTIAL USE IS OCCURRING ON THE NORTHEAST PORTION OF THE LAKE. THE DO WAS NEAR SATURATION THROUGHOUT THE WATER COLUMN AT THREE SAMPLING STATIONS. FLOATING AND SUBMERGED LOGS WERE OBSERVED LOCALLY AROUND THE LAKESHORE.



Cushman Lake, Mason County. September 14, 1971. Approx. scale 1:63,000.

LATITUDE 47°23'51" LONGITUDE 123°11'59" T22N-R4W-16
SKOKOMISH RIVER BASIN

PHYSICAL DATA

DRAINAGE AREA 99.2 SQ MI
ALTITUDE 475. FT
LAKE AREA 150. ACRES
LAKE VOLUME 8000. ACRE-FT
MEAN DEPTH 53. FT
MAXIMUM DEPTH 170. FT
SHORELINE LENGTH 4.5 MI
SHORELINE CONFIGURATION 2.6
DEVELOPMENT OF VOLUME 0.31
BOTTOM SLOPE 5.9 %
BASIN GEOLOGY IGNEOUS
INFLOW NONE VISIBLE
OUTFLOW CHANNEL PRESENT

CULTURAL DATA

RESIDENTIAL DEVELOPMENT 0 %
NUMBER OF NEARSHORE HOMES 0
LAND USE IN DRAINAGE BASIN
RESIDENTIAL URBAN 0 %
RESIDENTIAL SUBURBAN <1 %
AGRICULTURAL 0 %
FOREST OR UNPRODUCTIVE 93 %
LAKE SURFACE 7 %
PUBLIC BOAT ACCESS TO LAKE YES

WATER-QUALITY DATA (IN MG/L UNLESS OTHERWISE INDICATED)

SAMPLE SITE 1
DATE 8/26/74
TIME 1500 1505
DEPTH (FT) 3. 128.
TOTAL NITRATE (N) 0.02 0.03
TOTAL NITRITE (N) 0.00 0.00
TOTAL AMMONIA (N) 0.04 0.04
TOTAL ORGANIC NITROGEN (N) -- --
TOTAL PHOSPHORUS (P) 0.004 0.004
TOTAL ORTHOPHOSPHATE (P) 0.002 0.002
SPECIFIC CONDUCTANCE (MICROMHOS) 60 58
WATER TEMPERATURE (DEG C) 11.5 7.0
COLOR (PLATINUM-COBALT UNITS) 0 0
SECCHI-DISC VISIBILITY (FT) 28
DISSOLVED OXYGEN 10.2 8.6

LAKE SHORELINE COVERED BY EMERSED PLANTS
LAKE SURFACE COVERED BY EMERSED PLANTS

LITTLE OR NONE
NONE OR <1 %

DATE 8/26/74
TIME 1500
NUMBER OF FECAL COLIFORM SAMPLES 3
FECAL COLIFORM, MINIMUM (COL./100ML) <1
FECAL COLIFORM, MAXIMUM (COL./100ML) 2
FECAL COLIFORM, MEAN (COL./100ML) 1

REMARKS

AN ARTIFICIAL LAKE CREATED BY A DAM ON THE NORTH FORK SKOKOMISH RIVER. THE LAKE IS USED FOR HYDROPOWER BY THE CITY OF TACOMA. RESIDENTIAL DEVELOPMENT IS OCCURRING ON THE EAST AND SOUTH SHORES OF THE LAKE. THE DO WAS NEAR SATURATION THROUGHOUT THE WATER COLUMN.



Cushman, Lower Lake, Mason County. August 25, 1972. Approx. scale 1:12,000.

DEVEREAUX LAKE

MASON COUNTY

LATITUDE 47°24'47" LONGITUDE 122°50'47" T22N-R1W-7
 PUGET SOUND BASIN

PHYSICAL DATA

 DRAINAGE AREA 1.75 SQ MI
 ALTITUDE 215. FT
 LAKE AREA 94. ACRES
 LAKE VOLUME 1800. ACRE-FT
 MEAN DEPTH 19. FT
 MAXIMUM DEPTH 55. FT
 SHORELINE LENGTH 2.5 MI
 SHORELINE CONFIGURATION 1.8
 DEVELOPMENT OF VOLUME 0.35
 BOTTOM SLOPE 2.4 %
 BASIN GEOLOGY SED./META.
 INFLOW NONE VISIBLE
 OUTFLOW CHANNEL PRESENT

CULTURAL DATA

 RESIDENTIAL DEVELOPMENT 11 %
 NUMBER OF NEARSHORE HOMES 20
 LAND USE IN DRAINAGE BASIN
 RESIDENTIAL URBAN 0 %
 RESIDENTIAL SUBURBAN 1 %
 AGRICULTURAL 0 %
 FOREST OR UNPRODUCTIVE 91 %
 LAKE SURFACE 8 %
 PUBLIC BOAT ACCESS TO LAKE YES

WATER-QUALITY DATA (IN MG/L UNLESS OTHERWISE INDICATED)

SAMPLE SITE

 DATE 1
 8/27/74
 TIME 1400 1405
 DEPTH (FT) 3. 36.
 TOTAL NITRATE (N) 0.01 0.00
 TOTAL NITRITE (N) 0.00 0.00
 TOTAL AMMONIA (N) 0.06 0.05
 TOTAL ORGANIC NITROGEN (N) 0.23 0.17
 TOTAL PHOSPHORUS (P) 0.004 0.013
 TOTAL ORTHOPHOSPHATE (P) 0.002 0.004
 SPECIFIC CONDUCTANCE (MICROMHOS) 20 20
 WATER TEMPERATURE (DEG C) 21.8 10.0
 COLOR (PLATINUM-COBALT UNITS) 10 10
 SECCHI-DISC VISIBILITY (FT) 21
 DISSOLVED OXYGEN 8.8 4.0

LAKE SHORELINE COVERED BY EMERSED PLANTS
 LAKE SURFACE COVERED BY EMERSED PLANTS

76-100 %
 NONE OR <1 %

DATE

8/27/74

TIME

1400

NUMBER OF FECAL COLIFORM SAMPLES

3

FECAL COLIFORM, MINIMUM (COL./100ML)

<1

FECAL COLIFORM, MAXIMUM (COL./100ML)


4

FECAL COLIFORM, MEAN (COL./100ML)

2

REMARKS

 THE LAKESHORE IS PREDOMINATELY OCCUPIED BY A GIRL SCOUT CAMP. A SMALL PORTION OF THE NORTHEAST END OF THE LAKE IS RESIDENTIALLY DEVELOPED. THE SHORELINE WAS COVERED WITH A THIN MARGIN OF EMERSED PLANTS (SEDGE AND LILIES). THE DO WAS NEAR SATURATION EXCEPT FOR SOME DEPLETION NEAR THE LAKE BOTTOM.



0 1000 2000 FEET

EXPLANATION

— 20 —

Line of equal
water depth
Interval 10 feet

Devereaux Lake, Mason County. From Washington
Department of Game, June 9, 1949.



Devereaux Lake, Mason County. May 12, 1972. Approx. scale 1:12,000.

FAWN LAKE

MASON COUNTY

LATITUDE 47° 9'39" LONGITUDE 123° 3'43" T19N-R3W-4
 PUGET SOUND BASIN

PHYSICAL DATA

 DRAINAGE AREA 0.74 SQ MI
 ALTITUDE 160. FT
 LAKE AREA 56. ACRES
 LAKE VOLUME 460. ACRE-FT
 MEAN DEPTH 8. FT
 MAXIMUM DEPTH 22. FT
 SHORELINE LENGTH 2.3 MI
 SHORELINE CONFIGURATION 2.2
 DEVELOPMENT OF VOLUME 0.37
 BOTTOM SLOPE 1.2 %
 BASIN GEOLOGY SED./META.
 INFLOW INTERMITTENT
 OUTFLOW CHANNEL PRESENT

CULTURAL DATA

 RESIDENTIAL DEVELOPMENT 33 %
 NUMBER OF NEARSHORE HOMES 23
 LAND USE IN DRAINAGE BASIN
 RESIDENTIAL URBAN 0 %
 RESIDENTIAL SUBURBAN 10 %
 AGRICULTURAL 16 %
 FOREST OR UNPRODUCTIVE 62 %
 LAKE SURFACE 12 %
 PUBLIC BOAT ACCESS TO LAKE --

WATER-QUALITY DATA (IN MG/L UNLESS OTHERWISE INDICATED)

SAMPLE SITE


	1		2	
	8/20/74		8/20/74	
DATE	1030	1035	1115	1120
TIME	3.	8.	3.	8.
DEPTH (FT)	0.01	0.00	0.00	0.01
TOTAL NITRATE (N)	0.01	0.00	0.00	0.00
TOTAL NITRITE (N)	0.09	0.11	0.24	0.25
TOTAL AMMONIA (N)	0.75	0.63	0.59	0.64
TOTAL ORGANIC NITROGEN (N)	0.023	0.023	0.034	0.034
TOTAL PHOSPHORUS (P)	0.006	0.005	0.008	0.010
TOTAL ORTHOPHOSPHATE (P)	57	57	59	54
SPECIFIC CONDUCTANCE (MICROMHOS)	19.7	19.6	19.2	19.2
WATER TEMPERATURE (DEG C)	30	30	35	10
COLOR (PLATINUM-COBALT UNITS)	9		9	
SECCHI-DISC VISIBILITY (FT)	7.5	7.5	5.9	5.7
DISSOLVED OXYGEN				

LAKE SHORELINE COVERED BY EMERSED PLANTS 76-100 %
 LAKE SURFACE COVERED BY EMERSED PLANTS 1- 10 %

DATE 8/20/74
 TIME 1040
 NUMBER OF FECAL COLIFORM SAMPLES 4
 FECAL COLIFORM, MINIMUM (COL./100ML) <1
 FECAL COLIFORM, MAXIMUM (COL./100ML) 8
 FECAL COLIFORM, MEAN (COL./100ML) 3

REMARKS

 PRIOR TO 1965 THE LAKE WAS A SWAMPY AREA WITH SOME OPEN WATER. DREDGING OF THE AREA AND DAMMING OF THE OUTLET CREATED AN ARTIFICIAL LAKE FOR COMMUNITY RESIDENTIAL AND RECREATIONAL USE. THE LAKE IS PARTIALLY DIVIDED BY A DIKE WITH A NARROW CHANNEL AND WAS SAMPLED AT TWO SITES. EMERSED PLANTS COVERED MOST OF THE SHORELINE AND SUBMERSED PLANTS (WATER MILFOIL) COVERED THE LAKE BOTTOM. THE LITTORAL BOTTOM WAS SILT WITH SOME GRAVEL.



Fawn Lake, Mason County. From U.S. Geological
Survey, December 27, 1973.



Fawn Lake, Mason County. May 13, 1972. Approx. scale 1:12,000.

LATITUDE 47°11'22" LONGITUDE 122°58'13" T20N-R2W-30
 PUGET SOUND BASIN

PHYSICAL DATA

 DRAINAGE AREA 0.40 SQ MI
 ALTITUDE 95. FT
 LAKE AREA 39. ACRES
 LAKE VOLUME 730. ACRE-FT
 MEAN DEPTH 19. FT
 MAXIMUM DEPTH 30. FT
 SHORELINE LENGTH 1.0 MI
 SHORELINE CONFIGURATION 1.2
 DEVELOPMENT OF VOLUME 0.62
 BOTTOM SLOPE 2.0 %
 BASIN GEOLOGY SED./META.
 INFLOW NONE VISIBLE
 OUTFLOW CHANNEL ABSENT

CULTURAL DATA

 RESIDENTIAL DEVELOPMENT 0 %
 NUMBER OF NEARSHORE HOMES 0
 LAND USE IN DRAINAGE BASIN
 RESIDENTIAL URBAN 0 %
 RESIDENTIAL SUBURBAN 0 %
 AGRICULTURAL 14 %
 FOREST OR UNPRODUCTIVE 78 %
 LAKE SURFACE 8 %
 PUBLIC BOAT ACCESS TO LAKE --

WATER-QUALITY DATA (IN MG/L UNLESS OTHERWISE INDICATED)

SAMPLE SITE


 DATE 1
 8/20/74
 TIME 1205 1210
 DEPTH (FT) 3. 21.
 TOTAL NITRATE (N) 0.00 0.01
 TOTAL NITRITE (N) 0.01 0.00
 TOTAL AMMONIA (N) 0.07 0.27
 TOTAL ORGANIC NITROGEN (N) 0.92 0.53
 TOTAL PHOSPHORUS (P) 0.011 0.079
 TOTAL ORTHOPHOSPHATE (P) 0.004 0.045
 SPECIFIC CONDUCTANCE (MICROMHOS) 42 50
 WATER TEMPERATURE (DEG C) 19.1 8.3
 COLOR (PLATINUM-COBALT UNITS) 30 75
 SECCHI-DISC VISIBILITY (FT) 9
 DISSOLVED OXYGEN 8.6 0.4

LAKE SHORELINE COVERED BY EMERSED PLANTS 51- 75 %
 LAKE SURFACE COVERED BY EMERSED PLANTS NONE OR <1 %

DATE 8/20/74
 TIME 1220
 NUMBER OF FECAL COLIFORM SAMPLES 3
 FECAL COLIFORM, MINIMUM (COL./100ML) <1
 FECAL COLIFORM, MAXIMUM (COL./100ML) 2
 FECAL COLIFORM, MEAN (COL./100ML) 1

REMARKS

 THE SHORELAND ON THE NORTH SIDE OF THE LAKE IS USED FOR AGRICULTURE AND
 FOREST SURROUNDS THE REST OF THE LAKE. THIN PATCHES OF AQUATIC
 MACROPHYTES WERE OBSERVED. THE LITTORAL BOTTOM IS MOSTLY SILT AND MUCK.
 HYDROGEN SULFIDE WAS DETECTED IN THE HYPOLIMNION.



0 500 1000 FEET

EXPLANATION

—10—

Line of equal
water depth
Interval 5 feet

Forbes Lake, Mason County.

From U.S. Geological Survey, February 4, 1974.



Forbes Lake, Mason County. June 30, 1974. Approx. scale 1:4800.

HANKS LAKE

MASON COUNTY

LATITUDE 47°14'48" LONGITUDE 123°15' 5" T20N-R5W-1
 PUGET SOUND BASIN

PHYSICAL DATA

 DRAINAGE AREA 0.93 SQ MI
 ALTITUDE 400. FT
 LAKE AREA 26. ACRES
 LAKE VOLUME (EST.) 75. ACRE-FT
 MEAN DEPTH (EST.) 3. FT
 MAXIMUM DEPTH 5. FT
 SHORELINE LENGTH 1.6 MI
 SHORELINE CONFIGURATION 2.2
 DEVELOPMENT OF VOLUME 0.55
 BOTTOM SLOPE 0.43 %
 BASIN GEOLOGY SED./META.
 INFLOW NONE VISIBLE
 OUTFLOW CHANNEL ABSENT

CULTURAL DATA

 RESIDENTIAL DEVELOPMENT 0 %
 NUMBER OF NEARSHORE HOMES 0
 LAND USE IN DRAINAGE BASIN
 RESIDENTIAL URBAN 0 %
 RESIDENTIAL SUBURBAN 0 %
 AGRICULTURAL 0 %
 FOREST OR UNPRODUCTIVE 97 %
 LAKE SURFACE 3 %
 PUBLIC BOAT ACCESS TO LAKE YES

WATER-QUALITY DATA (IN MG/L UNLESS OTHERWISE INDICATED)


 SAMPLE SITE 1
 DATE 8/15/74
 TIME 1100 1105
 DEPTH (FT) 2. 3.
 TOTAL NITRATE (N) 0.01 0.01
 TOTAL NITRITE (N) 0.00 0.00
 TOTAL AMMONIA (N) 0.05 0.09
 TOTAL ORGANIC NITROGEN (N) 0.59 0.42
 TOTAL PHOSPHORUS (P) 0.012 0.014
 TOTAL ORTHOPHOSPHATE (P) 0.004 0.004
 SPECIFIC CONDUCTANCE (MICROMHOS) 36 36
 WATER TEMPERATURE (DEG C) 18.4 18.2
 COLOR (PLATINUM-COBALT UNITS) 5 5
 SECCHI-DISC VISIBILITY (FT) > 5
 DISSOLVED OXYGEN 9.3 9.2

LAKE SHORELINE COVERED BY EMERSED PLANTS 51- 75 %
 LAKE SURFACE COVERED BY EMERSED PLANTS 26- 50 %

DATE 8/15/74
 TIME 1115
 NUMBER OF FECAL COLIFORM SAMPLES 3
 FECAL COLIFORM, MINIMUM (COL./100ML) <1
 FECAL COLIFORM, MAXIMUM (COL./100ML) 1
 FECAL COLIFORM, MEAN (COL./100ML) 1

REMARKS

 THE LARGEST OF A GROUP OF SEVERAL SMALL LAKES. TREES AND SHRUBS OVERHANG THE WATER. THE LAKE HAD A HEAVY COVER OF BOTH EMERSED AND SUBMERSED PLANTS. THERE IS NO BATHYMETRIC MAP OF THE LAKE AND THE LAKE VOLUME HAS BEEN ESTIMATED.



Hanks Lake, Mason County. June 30, 1974. Approx. scale 1:4800.

LATITUDE 47°27'28" LONGITUDE 122°58'33" T23N-R2W-30
TAHUYA RIVER BASIN

PHYSICAL DATA

DRAINAGE AREA 1.13 SQ MI
ALTITUDE 366. FT
LAKE AREA 69. ACRES
LAKE VOLUME 1300. ACRE-FT
MEAN DEPTH 18. FT
MAXIMUM DEPTH 31. FT
SHORELINE LENGTH 2.2 MI
SHORELINE CONFIGURATION 1.8
DEVELOPMENT OF VOLUME 0.59
BOTTOM SLOPE 1.6 %
BASIN GEOLOGY SED./META.
INFLOW INTERMITTENT
OUTFLOW CHANNEL PRESENT

CULTURAL DATA

RESIDENTIAL DEVELOPMENT 72 %
NUMBER OF NEARSHORE HOMES 82
LAND USE IN DRAINAGE BASIN
RESIDENTIAL URBAN 0 %
RESIDENTIAL SUBURBAN 12 %
AGRICULTURAL 0 %
FOREST OR UNPRODUCTIVE 78 %
LAKE SURFACE 10 %
PUBLIC BOAT ACCESS TO LAKE YES

WATER-QUALITY DATA (IN MG/L UNLESS OTHERWISE INDICATED)


SAMPLE SITE 1
DATE 8/26/74
TIME 1100 1105
DEPTH (FT) 3. 23.
TOTAL NITRATE (N) 0.03 0.02
TOTAL NITRITE (N) 0.00 0.00
TOTAL AMMONIA (N) 0.11 0.11
TOTAL ORGANIC NITROGEN (N) 0.04 0.00
TOTAL PHOSPHORUS (P) 0.005 0.012
TOTAL ORTHOPHOSPHATE (P) 0.003 0.004
SPECIFIC CONDUCTANCE (MICROMHOS) 35 35
WATER TEMPERATURE (DEG C) 21.0 20.2
COLOR (PLATINUM-COBALT UNITS) 0 0
SECCHI-DISC VISIBILITY (FT) 18
DISSOLVED OXYGEN 9.2 9.0

LAKE SHORELINE COVERED BY EMERSED PLANTS 1- 10 %
LAKE SURFACE COVERED BY EMERSED PLANTS NONE OR <1 %

DATE 8/26/74
TIME 1030
NUMBER OF FECAL COLIFORM SAMPLES 4
FECAL COLIFORM, MINIMUM (COL./100ML) <1
FECAL COLIFORM, MAXIMUM (COL./100ML) 3
FECAL COLIFORM, MEAN (COL./100ML) 1

REMARKS

THE LAKE IS FED FROM WOOTEN LAKE. SUBMERSED PLANTS COVERED THE NORTH BAY. THE DO WAS NEAR SATURATION THROUGHOUT THE WATER COLUMN. THE LITTORAL BOTTOM IS MOSTLY GRAVEL AND SUPPORTED VERY FEW EMERSED AQUATIC PLANTS



N


0 1000 2000 FEET

EXPLANATION

—10—

Line of equal
water depth
Interval 5 feet

Haven Lake, Mason County. From Washington
Department of Game, July 20, 1948.



Haven Lake, Mason County. August 24, 1972. Approx. scale 1:12,000.

LATITUDE 47°10'36" LONGITUDE 123° 6'17" T20N-R3W-31
 PUGET SOUND BASIN

PHYSICAL DATA

 DRAINAGE AREA 17.5 SQ MI
 ALTITUDE 150. FT
 LAKE AREA 200. ACRES
 LAKE VOLUME 3200. ACRE-FT
 MEAN DEPTH 16. FT
 MAXIMUM DEPTH 23. FT
 SHORELINE LENGTH 2.5 MI
 SHORELINE CONFIGURATION 1.2
 DEVELOPMENT OF VOLUME 0.70
 BOTTOM SLOPE 0.70 %
 BASIN GEOLOGY SED./META.
 INFLOW PERENNIAL
 OUTFLOW CHANNEL PRESENT

CULTURAL DATA

 RESIDENTIAL DEVELOPMENT 28 %
 NUMBER OF NEARSHORE HOMES 38
 LAND USE IN DRAINAGE BASIN
 RESIDENTIAL URBAN 0 %
 RESIDENTIAL SUBURBAN 1 %
 AGRICULTURAL 5 %
 FOREST OR UNPRODUCTIVE 92 %
 LAKE SURFACE 2 %
 PUBLIC BOAT ACCESS TO LAKE YES

WATER-QUALITY DATA (IN MG/L UNLESS OTHERWISE INDICATED)


 SAMPLE SITE 1
 DATE 6/21/73
 TIME 1410 1415
 DEPTH (FT) 3. 17.
 TOTAL NITRATE (N) 0.01 0.01
 TOTAL NITRITE (N) 0.00 0.00
 TOTAL AMMONIA (N) 0.08 0.09
 TOTAL ORGANIC NITROGEN (N) 0.07 0.03
 TOTAL PHOSPHORUS (P) 0.010 0.024
 DISSOLVED ORTHOPHOSPHATE (P) 0.001 --
 SPECIFIC CONDUCTANCE (MICROMHOS) 78 78
 WATER TEMPERATURE (DEG C) 20.0 15.3
 COLOR (PLATINUM-COBALT UNITS) 10 10
 SECCHI-DISC VISIBILITY (FT) 10
 DISSOLVED OXYGEN 10.5 8.1

LAKE SHORELINE COVERED BY EMERSED PLANTS 76-100 %
 LAKE SURFACE COVERED BY EMERSED PLANTS 1- 10 %

DATE 6/21/73
 TIME 1430
 NUMBER OF FECAL COLIFORM SAMPLES 4
 FECAL COLIFORM, MINIMUM (COL./100ML) <1
 FECAL COLIFORM, MAXIMUM (COL./100ML) 2
 FECAL COLIFORM, MEAN (COL./100ML) <1

REMARKS

 THE LAKE IS FED BY GOSNELL CREEK, A STREAM WHICH MEANDERS THROUGH SEVERAL MILES OF AGRICULTURAL LAND. THE SOUTHWEST AND NORTHEAST ENDS OF THE LAKE NEAR THE INFLOW AND OUTFLOW ARE MARSHY. DENSE BEDS OF EMERSED PLANTS EXTEND 200-300 FEET FROM SHORE NEAR THE MARSHES. SUBMERSED PLANTS (ELODEA AND PONDWEED) COVERED ABOUT 30 PERCENT OF THE LAKE BOTTOM. IN 1973 THE U.S. GEOLOGICAL SURVEY SAMPLED THE LAKE FOUR TIMES. THE PLANT SURVEY WAS MADE ON AUGUST 12, 1973.



Isabella Lake, Mason County. From Washington
Department of Game, June 25, 1952.



Isabella Lake, Mason County. May 19, 1972. Approx. scale 1:12,000.

ISLAND LAKE

MASON COUNTY

LATITUDE 47°14'44" LONGITUDE 123° 6'40" T20N-R3W-6
 PUGET SOUND BASIN

PHYSICAL DATA

 DRAINAGE AREA 0.26 SQ MI
 ALTITUDE 230. FT
 LAKE AREA 110. ACRES
 LAKE VOLUME 2200. ACRE-FT
 MEAN DEPTH 21. FT
 MAXIMUM DEPTH 31. FT
 SHORELINE LENGTH 1.7 MI
 SHORELINE CONFIGURATION 1.2
 DEVELOPMENT OF VOLUME 0.67
 BOTTOM SLOPE 1.3 %
 BASIN GEOLOGY SED./META.
 INFLOW NONE VISIBLE
 OUTFLOW CHANNEL PRESENT

CULTURAL DATA

 RESIDENTIAL DEVELOPMENT 100 %
 NUMBER OF NEARSHORE HOMES 85
 LAND USE IN DRAINAGE BASIN
 RESIDENTIAL URBAN 0 %
 RESIDENTIAL SUBURBAN 35 %
 AGRICULTURAL 0 %
 FOREST OR UNPRODUCTIVE 0 %
 LAKE SURFACE 65 %
 PUBLIC BOAT ACCESS TO LAKE YES

WATER-QUALITY DATA (IN MG/L UNLESS OTHERWISE INDICATED)


 SAMPLE SITE 1
 DATE 8/16/74
 TIME 1115 1120
 DEPTH (FT) 3. 18.
 TOTAL NITRATE (N) 0.01 0.01
 TOTAL NITRITE (N) 0.00 0.00
 TOTAL AMMONIA (N) 0.05 0.05
 TOTAL ORGANIC NITROGEN (N) 0.41 0.40
 TOTAL PHOSPHORUS (P) 0.011 0.010
 TOTAL ORTHOPHOSPHATE (P) 0.003 0.003
 SPECIFIC CONDUCTANCE (MICROMHOS) 40 40
 WATER TEMPERATURE (DEG C) 20.8 20.0
 COLOR (PLATINUM-COBALT UNITS) 0 0
 SECCHI-DISC VISIBILITY (FT) 11
 DISSOLVED OXYGEN 8.9 8.3

LAKE SHORELINE COVERED BY EMERSED PLANTS 11- 25 %
 LAKE SURFACE COVERED BY EMERSED PLANTS NONE OR <1 %

DATE 8/16/74
 TIME 1130
 NUMBER OF FECAL COLIFORM SAMPLES 3
 FECAL COLIFORM, MINIMUM (COL./100ML) 2
 FECAL COLIFORM, MAXIMUM (COL./100ML) 3
 FECAL COLIFORM, MEAN (COL./100ML) 2

REMARKS

 A DENSE PATTERN OF RESIDENTIAL DEVELOPMENT SURROUNDS THE LAKE. THE LAKE HAS A STEEP-SIDED, GRAVELLY LITTORAL BOTTOM WHICH SUPPORTED A SPARSE GROWTH OF AQUATIC MACROPHYTES. THE DO WAS NEAR SATURATION THROUGHOUT THE WATER COLUMN.



Island Lake, Mason County. From Washington
Department of Game, February 15, 1952.



Island Lake, Mason County. July 13, 1974. Approx. scale 1:4800.

LIMERICK LAKE

MASON COUNTY

LATITUDE 47°16'59" LONGITUDE 123° 2'51" T21N-R3W-27
 PUGET SOUND BASIN

PHYSICAL DATA

 DRAINAGE AREA 13.0 SQ MI
 ALTITUDE 230. FT
 LAKE AREA 130. ACRES
 LAKE VOLUME 1200. ACRE-FT
 MEAN DEPTH 9. FT
 MAXIMUM DEPTH 24. FT
 SHORELINE LENGTH 4.4 MI
 SHORELINE CONFIGURATION 2.8
 DEVELOPMENT OF VOLUME 0.39
 BOTTOM SLOPE 0.90 %
 BASIN GEOLOGY SED./META.
 INFLOW NONE VISIBLE
 OUTFLOW CHANNEL PRESENT

CULTURAL DATA

 RESIDENTIAL DEVELOPMENT 31 %
 NUMBER OF NEARSHORE HOMES 24
 LAND USE IN DRAINAGE BASIN
 RESIDENTIAL URBAN 0 %
 RESIDENTIAL SUBURBAN 1 %
 AGRICULTURAL 0 %
 FOREST OR UNPRODUCTIVE 95 %
 LAKE SURFACE 4 %
 PUBLIC BOAT ACCESS TO LAKE YES

WATER-QUALITY DATA (IN MG/L UNLESS OTHERWISE INDICATED)


 SAMPLE SITE 1
 DATE 8/16/74
 TIME 1300 1305
 DEPTH (FT) 3. 11.
 TOTAL NITRATE (N) 0.02 0.01
 TOTAL NITRITE (N) 0.00 0.00
 TOTAL AMMONIA (N) 0.05 0.06
 TOTAL ORGANIC NITROGEN (N) 0.45 0.49
 TOTAL PHOSPHORUS (P) 0.008 0.011
 TOTAL ORTHOPHOSPHATE (P) 0.004 0.003
 SPECIFIC CONDUCTANCE (MICROMHOS) 55 55
 WATER TEMPERATURE (DEG C) 20.3 19.1
 COLOR (PLATINUM-COBALT UNITS) 20 15
 SECCHI-DISC VISIBILITY (FT) 11
 DISSOLVED OXYGEN 8.2 7.3

LAKE SHORELINE COVERED BY EMERSED PLANTS 11- 25 %
 LAKE SURFACE COVERED BY EMERSED PLANTS NONE OR <1 %

DATE 8/16/74
 TIME 1315
 NUMBER OF FECAL COLIFORM SAMPLES 4
 FECAL COLIFORM, MINIMUM (COL./100ML) 5
 FECAL COLIFORM, MAXIMUM (COL./100ML) 9
 FECAL COLIFORM, MEAN (COL./100ML) 8

REMARKS

 AN ARTIFICIAL LAKE FED FROM CRANBERRY LAKE. THE SHORE AND UPLAND ARE DEVELOPED FOR RESIDENTIAL AND RECREATIONAL PURPOSES. EMERSED PLANTS WERE THINLY SCATTERED ALONG THE GRAVELLY BEACHES. SUBMERSED PLANTS OCCURRED IN BOTH THINLY SCATTERED AND DENSE PATCHES.



Limerick Lake, Mason County. From
U.S. Geological Survey, December 4, 1973.



Limerick Lake, Mason County. May 12, 1972. Approx. scale 1:12,000.

LOST LAKE

MASON COUNTY

LATITUDE 47° 9'16" LONGITUDE 123°14'51" T19N-R5W-1
 PUGET SOUND BASIN

PHYSICAL DATA

 DRAINAGE AREA 1.08 SQ MI
 ALTITUDE 480. FT
 LAKE AREA 120. ACRES
 LAKE VOLUME 3400. ACRE-FT
 MEAN DEPTH 28. FT
 MAXIMUM DEPTH 65. FT
 SHORELINE LENGTH 3.2 MI
 SHORELINE CONFIGURATION 2.1
 DEVELOPMENT OF VOLUME 0.42
 BOTTOM SLOPE 2.5 %
 BASIN GEOLOGY SED./META.
 INFLOW NONE VISIBLE
 OUTFLOW CHANNEL ABSENT

CULTURAL DATA

 RESIDENTIAL DEVELOPMENT 95 %
 NUMBER OF NEARSHORE HOMES 114
 LAND USE IN DRAINAGE BASIN
 RESIDENTIAL URBAN 0 %
 RESIDENTIAL SUBURBAN 12 %
 AGRICULTURAL 0 %
 FOREST OR UNPRODUCTIVE 70 %
 LAKE SURFACE 18 %
 PUBLIC BOAT ACCESS TO LAKE YES

WATER-QUALITY DATA (IN MG/L UNLESS OTHERWISE INDICATED)



 SAMPLE SITE 1
 DATE 6/21/73
 TIME 1135 1145
 DEPTH (FT) 3. 52.
 TOTAL NITRATE (N) 0.01 0.01
 TOTAL NITRITE (N) 0.00 0.00
 TOTAL AMMONIA (N) 0.05 0.01
 TOTAL ORGANIC NITROGEN (N) 0.06 0.12
 TOTAL PHOSPHORUS (P) 0.016 0.004
 DISSOLVED ORTHOPHOSPHATE (P) 0.001 0.000
 SPECIFIC CONDUCTANCE (MICROMHOS) 21 22
 WATER TEMPERATURE (DEG C) 19.1 6.0
 COLOR (PLATINUM-COBALT UNITS) 5 10
 SECCHI-DISC VISIBILITY (FT) 21
 DISSOLVED OXYGEN 9.1 4.4

LAKE SHORELINE COVERED BY EMERSED PLANTS LITTLE OR NONE
 LAKE SURFACE COVERED BY EMERSED PLANTS NONE OR <1 %

DATE 6/21/73
 TIME 1200
 NUMBER OF FECAL COLIFORM SAMPLES 4
 FECAL COLIFORM, MINIMUM (COL./100ML) <1
 FECAL COLIFORM, MAXIMUM (COL./100ML) 2
 FECAL COLIFORM, MEAN (COL./100ML) <1

REMARKS


 THE LAKE RECEIVES HEAVY RECREATIONAL USE. NO AQUATIC MACROPHYTES WERE OBSERVED. THE LITTORAL BOTTOM IS GRAVEL, COBBLE AND SAND. DO WAS NEAR SATURATION THROUGHOUT THE WATER COLUMN EXCEPT FOR FOUR FEET OF WATER NEAR THE LAKE BOTTOM. IN 1973 THE U.S. GEOLOGICAL SURVEY SAMPLED THE LAKE FOUR TIMES. THE PLANT SURVEY WAS MADE ON AUGUST 12, 1973.



EXPLANATION

— 20 —
 Line of equal
 water depth
 Interval 10 feet

Lost Lake, Mason County. From Washington
 Department of Game, February 12, 1952.



Lost Lake, Mason County. May 19, 1972. Approx. scale 1:12,000.

LYSTAIR LAKE

MASON COUNTY

LATITUDE 47° 9' 7" LONGITUDE 123°19'50" T19N-R5W-8
CHEHALIS RIVER BASIN

PHYSICAL DATA

DRAINAGE AREA 0.24 SQ MI
ALTITUDE 350. FT
LAKE AREA 46. ACRES
LAKE VOLUME 230. ACRE-FT
MEAN DEPTH 5. FT
MAXIMUM DEPTH 9. FT
SHORELINE LENGTH 2.1 MI
SHORELINE CONFIGURATION 2.2
DEVELOPMENT OF VOLUME 0.56
BOTTOM SLOPE 0.56 %
BASIN GEOLOGY SED./META.
INFLOW NONE VISIRLE
OUTFLOW CHANNEL PRESENT

CULTURAL DATA

RESIDENTIAL DEVELOPMENT 29 %
NUMBER OF NEARSHORE HOMES 19
LAND USE IN DRAINAGE BASIN
RESIDENTIAL URBAN 0 %
RESIDENTIAL SUBURBAN 7 %
AGRICULTURAL 7 %
FOREST OR UNPRODUCTIVE 56 %
LAKE SURFACE 30 %
PUBLIC BOAT ACCESS TO LAKE --

WATER-QUALITY DATA (IN MG/L UNLESS OTHERWISE INDICATED)

SAMPLE SITE


1
DATE 8/15/74
TIME 1245 1250
DEPTH (FT) 3. 5.
TOTAL NITRATE (N) 0.01 0.01
TOTAL NITRITE (N) 0.00 0.00
TOTAL AMMONIA (N) 0.10 0.10
TOTAL ORGANIC NITROGEN (N) 0.41 0.40
TOTAL PHOSPHORUS (P) 0.012 0.013
TOTAL ORTHOPHOSPHATE (P) 0.004 0.004
SPECIFIC CONDUCTANCE (MICROMHOS) 33 33
WATER TEMPERATURE (DEG C) 19.1 18.8
COLOR (PLATINUM-COBALT UNITS) 15 15
SECCHI-DISC VISIRILITY (FT) 6
DISSOLVED OXYGEN 8.8 8.8

LAKE SHORELINE COVERED BY EMERSED PLANTS 76-100 %
LAKE SURFACE COVERED BY EMERSED PLANTS 11- 25 %

DATE 8/15/74
TIME 1300
NUMBER OF FECAL COLIFORM SAMPLES 3
FECAL COLIFORM, MINIMUM (COL./100ML) <1
FECAL COLIFORM, MAXIMUM (COL./100ML) 3
FECAL COLIFORM, MEAN (COL./100ML) 1

REMARKS

A VERY SHALLOW LAKE WITH TWO BOG MAT ISLANDS. EMERSED PLANTS COVERED THE SHORELINE AND A LARGE PERCENTAGE OF THE LAKE SURFACE. PARK FACILITIES AND A GOLF COURSE ARE LOCATED ON THE SOUTHERN END OF THE LAKE.



Lystair Lake, Mason County. From
U.S. Geological Survey, December 28, 1973.



Lystair Lake, Mason County. June 30, 1974. Approx. scale 1:4800.

MAGGIE LAKE

MASON COUNTY

LATITUDE 47°24' 0" LONGITUDE 123° 1'40" T22N-R3W-14
TAHUYA RIVER BASIN

PHYSICAL DATA

DRAINAGE AREA 0.24 SQ MI
ALTITUDE 400. FT
LAKE AREA 25. ACRES
LAKE VOLUME 820. ACRE-FT
MEAN DEPTH 33. FT
MAXIMUM DEPTH 74. FT
SHORELINE LENGTH 1.1 MI
SHORELINE CONFIGURATION 1.5
DEVELOPMENT OF VOLUME 0.44
BOTTOM SLOPE 6.3 %
BASIN GEOLOGY SED./META.
INFLOW NONE VISIBLE
OUTFLOW CHANNEL ABSENT

CULTURAL DATA

RESIDENTIAL DEVELOPMENT 52 %
NUMBER OF NEARSHORE HOMES 31
LAND USE IN DRAINAGE BASIN
RESIDENTIAL URBAN 0 %
RESIDENTIAL SUBURBAN 27 %
AGRICULTURAL 0 %
FOREST OR UNPRODUCTIVE 46 %
LAKE SURFACE 27 %
PUBLIC BOAT ACCESS TO LAKE YES

WATER-QUALITY DATA (IN MG/L UNLESS OTHERWISE INDICATED)


SAMPLE SITE 1
DATE 8/26/74
TIME 1400 1405
DEPTH (FT) 3. 59.
TOTAL NITRATE (N) 0.00 0.00
TOTAL NITRITE (N) 0.00 0.00
TOTAL AMMONIA (N) 0.05 0.04
TOTAL ORGANIC NITROGEN (N) 0.04 --
TOTAL PHOSPHORUS (P) 0.007 0.008
TOTAL ORTHOPHOSPHATE (P) 0.003 0.005
SPECIFIC CONDUCTANCE (MICROMHOS) 17 19
WATER TEMPERATURE (DEG C) 21.0 7.0
COLOR (PLATINUM-COBALT UNITS) 0 0
SECCHI-DISC VISIBILITY (FT) 25
DISSOLVED OXYGEN 8.9 8.6

LAKE SHORELINE COVERED BY EMERSED PLANTS LITTLE OR NONE
LAKE SURFACE COVERED BY EMERSED PLANTS NONE OR <1 %

DATE 8/26/74
TIME 1330
NUMBER OF FECAL COLIFORM SAMPLES 4
FECAL COLIFORM, MINIMUM (COL./100ML) <1
FECAL COLIFORM, MAXIMUM (COL./100ML) 5
FECAL COLIFORM, MEAN (COL./100ML) 2

REMARKS

A DEEP LAKE IN RELATION TO THE SURFACE AREA. THE WATER CLARITY IS HIGH AS INDICATED BY A SECCHI-DISC READING OF 25 FEET. THE DO WAS NEAR SATURATION THROUGHOUT THE WATER COLUMN. VERY FEW AQUATIC MACROPHYTES WERE GROWING ON THE GRAVELLY LITTORAL BOTTOM. HOWEVER, MOSS WAS FOUND GROWING ON THE LAKE BOTTOM AT A DEPTH OF 64 FEET.



N



0 500 1000 FEET

EXPLANATION

— 20 —

Line of equal
water depth
Interval 10 feet

Maggie Lake, Mason County. From Washington
Department of Game, June 11, 1950.



Maggie Lake, Mason County. July 13, 1974. Approx. scale 1:4800.

MASON LAKE

MASON COUNTY

LATITUDE 47°21'14" LONGITUDE 122°55'17" T22N-R2W-34
 PUGET SOUND BASIN

PHYSICAL DATA

 DRAINAGE AREA 20.2 SQ MI
 ALTITUDE 194. FT
 LAKE AREA 1000. ACRES
 LAKE VOLUME 49000. ACRE-FT
 MEAN DEPTH 48. FT
 MAXIMUM DEPTH 90. FT
 SHORELINE LENGTH 11. MI
 SHORELINE CONFIGURATION 2.4
 DEVELOPMENT OF VOLUME 0.53
 BOTTOM SLOPE 1.2 %
 BASIN GEOLOGY SED./META.
 INFLOW PERENNIAL
 OUTFLOW CHANNEL PRESENT

CULTURAL DATA

 RESIDENTIAL DEVELOPMENT 87 %
 NUMBER OF NEARSHORE HOMES 571
 LAND USE IN DRAINAGE BASIN
 RESIDENTIAL URBAN 0 %
 RESIDENTIAL SUBURBAN 3 %
 AGRICULTURAL 0 %
 FOREST OR UNPRODUCTIVE 89 %
 LAKE SURFACE 8 %
 PUBLIC BOAT ACCESS TO LAKE YES

WATER-QUALITY DATA (IN MG/L UNLESS OTHERWISE INDICATED)

SAMPLE SITE

 DATE 1
 TIME 6/29/72
 DEPTH (FT) 1010 1020
 DISSOLVED NITRATE (N) 3. 75.
 DISSOLVED NITRITE (N) 0.00 0.00
 TOTAL AMMONIA (N) 0.00 0.00
 TOTAL ORGANIC NITROGEN (N) 0.19 0.14
 TOTAL PHOSPHORUS (P) 0.012 0.014
 DISSOLVED ORTHOPHOSPHATE (P) 0.000 0.000
 SPECIFIC CONDUCTANCE (MICROMHOS) 42 42
 WATER TEMPERATURE (DEG C) 17.1 9.5
 COLOR (PLATINUM-COBALT UNITS) 15 15
 SECCHI-DISC VISIBILITY (FT) 14
 DISSOLVED OXYGEN 9.9 6.5

LAKE SHORELINE COVERED BY EMERSED PLANTS

1- 10 %

LAKE SURFACE COVERED BY EMERSED PLANTS

NONE OR <1 %

DATE

6/29/72

TIME

1030

NUMBER OF FECAL COLIFORM SAMPLES

5

FECAL COLIFORM, MINIMUM (COL./100ML)

<1

FECAL COLIFORM, MAXIMUM (COL./100ML)


2

FECAL COLIFORM, MEAN (COL./100ML)

1

REMARKS

 THE LARGEST AND DEEPEST NATURAL LAKE IN MASON COUNTY. THE LAKE IS FED BY SHUMOCHER CREEK, A PERENNIAL STREAM. A LARGE PARK, RECREATIONAL FACILITIES, AND TWO MARINAS ARE LOCATED ON THE LAKE. MOST OF THE AQUATIC MACROPHYTES WERE OBSERVED IN THE NARROW ARM ON THE NORTH END OF THE LAKE. THE DO WAS DEPLETED ONLY SLIGHTLY IN THE HYPOLIMNION. THE U.S. GEOLOGICAL SURVEY HAS MAINTAINED A LAKE-STAGE RECORDER ON THE LAKE SINCE 1951. IN 1972 THE U.S. GEOLOGICAL SURVEY SAMPLED THE LAKE FOUR TIMES. THE PLANT SURVEY WAS MADE ON OCTOBER 5, 1972.



Mason Lake, Mason County. From Washington
Department of Game, May 4, 1954.



Mason Lake, Mason County. August 9, 1972. Approx. scale 1:29,000.

MELBOURNE LAKE

MASON COUNTY

LATITUDE 47°29'55" LONGITUDE 123° 7'19" T23N-R4W-7
SKOKOMISH RIVER BASIN

PHYSICAL DATA

CULTURAL DATA

-----		-----	
DRAINAGE AREA	2.17 SQ MI	RESIDENTIAL DEVELOPMENT	0 %
ALTITUDE	730. FT		
LAKE AREA	35. ACRES	NUMBER OF NEARSHORE HOMES	0
LAKE VOLUME	240. ACRE-FT		
MEAN DEPTH	7. FT	LAND USE IN DRAINAGE BASIN	
MAXIMUM DEPTH	12. FT		
SHORELINE LENGTH	1.3 MI	RESIDENTIAL URBAN	0 %
SHORELINE CONFIGURATION	1.6	RESIDENTIAL SUBURBAN	0 %
DEVELOPMENT OF VOLUME	0.56	AGRICULTURAL	0 %
BOTTOM SLOPE	0.86 %	FOREST OR UNPRODUCTIVE	97 %
BASIN GEOLOGY	IGNEOUS	LAKE SURFACE	3 %
INFLOW	PERENNIAL		
OUTFLOW CHANNEL	PRESENT	PUBLIC BOAT ACCESS TO LAKE	YES

WATER-QUALITY DATA (IN MG/L UNLESS OTHERWISE INDICATED)



SAMPLE SITE	1
DATE	8/21/74
TIME	1450 1455
DEPTH (FT)	3. 7.
TOTAL NITRATE (N)	0.02 0.02
TOTAL NITRITE (N)	0.00 0.00
TOTAL AMMONIA (N)	0.05 0.05
TOTAL ORGANIC NITROGEN (N)	0.50 0.59
TOTAL PHOSPHORUS (P)	0.010 0.011
TOTAL ORTHOPHOSPHATE (P)	0.004 0.004
SPECIFIC CONDUCTANCE (MICROMHOS)	19 19
WATER TEMPERATURE (DEG C)	19.6 19.3
COLOR (PLATINUM-COBALT UNITS)	5 5
SECCHI-DISC VISIBILITY (FT)	> 8
DISSOLVED OXYGEN	8.5 8.9

LAKE SHORELINE COVERED BY EMERSED PLANTS	76-100 %
LAKE SURFACE COVERED BY EMERSED PLANTS	51- 75 %

DATE	8/21/74
TIME	1500
NUMBER OF FECAL COLIFORM SAMPLES	3
FECAL COLIFORM, MINIMUM (COL./100ML)	<1
FECAL COLIFORM, MAXIMUM (COL./100ML)	4
FECAL COLIFORM, MEAN (COL./100ML)	3

REMARKS

A SHALLOW LAKE CHOKED WITH EMERSED AND SUBMERSED AQUATIC VEGETATION. MOST OF THE LAKE BOTTOM WAS COVERED WITH EMERSED PLANTS (PONDWEED). THE LITTORAL BOTTOM IS MUCK AND LITTERED WITH LOGS AND WOOD DEBRIS. THE LAKE WAS USED AT ONE TIME AS A REARING POND FOR SILVER SALMON BY THE DEPARTMENT OF FISHERIES.



Melbourne Lake, Mason County. From Washington
Department of Game, May 4, 1954.



Melbourne Lake, Mason County. August 25, 1972. Approx. scale 1:12,000.

NAHWATZEL LAKE

MASON COUNTY

LATITUDE 47°14' 8" LONGITUDE 123°20' 8" T20N-R5W-8
CHEHALIS RIVER BASIN

PHYSICAL DATA

DRAINAGE AREA 6.20 SQ MI
ALTITUDE 440. FT
LAKE AREA 270. ACRES
LAKE VOLUME 4600. ACRE-FT
MEAN DEPTH 17. FT
MAXIMUM DEPTH 25. FT
SHORELINE LENGTH 2.9 MI
SHORELINE CONFIGURATION 1.3
DEVELOPMENT OF VOLUME 0.69
BOTTOM SLOPE 0.65 %
BASIN GEOLOGY SED./META.
INFLOW PERENNIAL
OUTFLOW CHANNEL PRESENT

CULTURAL DATA

RESIDENTIAL DEVELOPMENT 51 %
NUMBER OF NEARSHORE HOMES 86
LAND USE IN DRAINAGE BASIN
RESIDENTIAL URBAN 0 %
RESIDENTIAL SUBURBAN 2 %
AGRICULTURAL 0 %
FOREST OR UNPRODUCTIVE 91 %
LAKE SURFACE 7 %
PUBLIC BOAT ACCESS TO LAKE YES

WATER-QUALITY DATA (IN MG/L UNLESS OTHERWISE INDICATED)

SAMPLE SITE


DATE 8/15/74
TIME 1155 1200
DEPTH (FT) 3. 20.
TOTAL NITRATE (N) 0.01 0.01
TOTAL NITRITE (N) 0.00 0.00
TOTAL AMMONIA (N) 0.05 0.05
TOTAL ORGANIC NITROGEN (N) 0.24 0.19
TOTAL PHOSPHORUS (P) 0.007 0.007
TOTAL ORTHOPHOSPHATE (P) 0.002 0.002
SPECIFIC CONDUCTANCE (MICROMHOS) 21 21
WATER TEMPERATURE (DEG C) 19.8 19.3
COLOR (PLATINUM-COBALT UNITS) 0 0
SECCHI-DISC VISIBILITY (FT) 18
DISSOLVED OXYGEN 8.7 8.6

LAKE SHORELINE COVERED BY EMERSED PLANTS 26- 50 %
LAKE SURFACE COVERED BY EMERSED PLANTS NONE OR <1 %

DATE 8/15/74
TIME 1210
NUMBER OF FECAL COLIFORM SAMPLES 4
FECAL COLIFORM, MINIMUM (COL./100ML) <1
FECAL COLIFORM, MAXIMUM (COL./100ML) <1
FECAL COLIFORM, MEAN (COL./100ML) <1

REMARKS

A LARGE NATURAL LAKE WITH A PARTIALLY UNDEVELOPED SHORELINE. THE LITTORAL ZONE IS MOSTLY GRAVEL AND SUPPORTED A SPARSE GROWTH OF EMERSED PLANTS. SUBMERSED PLANTS (CHARA) WERE GROWING IN DEEP WATER AS INDICATED BY PLANTS ATTACHED TO THE ANCHOR AT A DEPTH OF 24 FEET. THE DO WAS NEAR SATURATION THROUGHOUT THE WATER COLUMN. LOG PILINGS STAND AT THE NORTHEAST END OF THE LAKE. FLOATING AND SUBMERGED LOGS WERE OBSERVED ALONG THE NORTHWEST SHORE.



N



0 1000 2000 FEET



EXPLANATION

— 10 —

Line of equal
water depth
Interval 5 feet

Nahwatzel Lake, Mason County. From Washington
Department of Game, June 7, 1949.



Nahwatzel Lake, Mason County. August 27, 1972. Approx. scale 1:12,000.

PHILLIPS LAKE

MASON COUNTY

LATITUDE 47°14'52" LONGITUDE 122°57'52" T20N-R2W-5
 PUGET SOUND BASIN

PHYSICAL DATA

 DRAINAGE AREA 0.50 SQ MI
 ALTITUDE 188. FT
 LAKE AREA 110. ACRES
 LAKE VOLUME 1800. ACRE-FT
 MEAN DEPTH 16. FT
 MAXIMUM DEPTH 25. FT
 SHORELINE LENGTH 2.6 MI
 SHORELINE CONFIGURATION 1.8
 DEVELOPMENT OF VOLUME 0.63
 BOTTOM SLOPE 0.99 %
 BASIN GEOLOGY SED./META.
 INFLOW NONE VISIBL
 OUTFLOW CHANNEL PRESENT

CULTURAL DATA

 RESIDENTIAL DEVELOPMENT 100 %
 NUMBER OF NEARSHORE HOMES 125
 LAND USE IN DRAINAGE BASIN
 RESIDENTIAL URBAN 0 %
 RESIDENTIAL SUBURBAN 30 %
 AGRICULTURAL 0 %
 FOREST OR UNPRODUCTIVE 35 %
 LAKE SURFACE 35 %
 PUBLIC BOAT ACCESS TO LAKE YES

WATER-QUALITY DATA (IN MG/L UNLESS OTHERWISE INDICATED)


 SAMPLE SITE 1
 DATE 6/29/72
 TIME 1340 1350
 DEPTH (FT) 3. 16.
 DISSOLVED NITRATE (N) 0.00 0.00
 DISSOLVED NITRITE (N) 0.00 0.00
 TOTAL AMMONIA (N) 0.03 0.06
 TOTAL ORGANIC NITROGEN (N) 0.30 0.37
 TOTAL PHOSPHORUS (P) 0.015 0.038
 DISSOLVED ORTHOPHOSPHATE (P) 0.032 0.032
 SPECIFIC CONDUCTANCE (MICROMHOS) 20 20
 WATER TEMPERATURE (DEG C) 19.7 18.5
 COLOR (PLATINUM-COBALT UNITS) 10 10
 SECCHI-DISC VISIBILITY (FT) 16
 DISSOLVED OXYGEN 9.1 8.5

LAKE SHORELINE COVERED BY EMERSED PLANTS LITTLE OR NONE
 LAKE SURFACE COVERED BY EMERSED PLANTS NONE OR <1 %

DATE 6/29/72
 TIME 1400
 NUMBER OF FECAL COLIFORM SAMPLES 4
 FECAL COLIFORM, MINIMUM (COL./100ML) <1
 FECAL COLIFORM, MAXIMUM (COL./100ML) <1
 FECAL COLIFORM, MEAN (COL./100ML) <1

REMARKS

 VERY FEW ROOTED AQUATIC PLANTS WERE FOUND GROWING ON THE SAND AND GRAVEL
 LITTORAL BOTTOM. IN 1972 THE U.S. GEOLOGICAL SURVEY SAMPLED THE LAKE
 FOUR TIMES. THE PLANT SURVEY WAS MADE ON OCTOBER 17, 1972.



N



0 1000 2000 FEET



EXPLANATION

— 10 —

Line of equal
water depth
Interval 5 feet

Phillips Lake, Mason County. From Washington
Department of Game, February 14, 1952.



Phillips Lake, Mason County. August 9, 1972. Approx. scale 1:7900.

PRICE LAKE

MASON COUNTY

LATITUDE 47°28'23" LONGITUDE 123° 9'37" T23N-R4W-23
 PUGET SOUND BASIN

PHYSICAL DATA

 DRAINAGE AREA 3.91 SQ MI
 ALTITUDE 780. FT
 LAKE AREA 62. ACRES
 LAKE VOLUME 380. ACRE-FT
 MEAN DEPTH 6. FT
 MAXIMUM DEPTH 16. FT
 SHORELINE LENGTH 2.0 MI
 SHORELINE CONFIGURATION 1.8
 DEVELOPMENT OF VOLUME 0.38
 BOTTOM SLOPE 0.86 %
 BASIN GEOLOGY IGNEOUS
 INFLOW INTERMITTENT
 OUTFLOW CHANNEL PRESENT

CULTURAL DATA

 RESIDENTIAL DEVELOPMENT 0 %
 NUMBER OF NEARSHORE HOMES 0
 LAND USE IN DRAINAGE BASIN
 RESIDENTIAL URBAN 0 %
 RESIDENTIAL SUBURBAN 0 %
 AGRICULTURAL 0 %
 FOREST OR UNPRODUCTIVE 98 %
 LAKE SURFACE 2 %
 PUBLIC BOAT ACCESS TO LAKE --

WATER-QUALITY DATA (IN MG/L UNLESS OTHERWISE INDICATED)

SAMPLE SITE


 DATE 8/21/74
 TIME 1405 1410
 DEPTH (FT) 3. 7.
 TOTAL NITRATE (N) 0.02 0.03
 TOTAL NITRITE (N) 0.00 0.00
 TOTAL AMMONIA (N) 0.05 0.06
 TOTAL ORGANIC NITROGEN (N) 0.31 0.38
 TOTAL PHOSPHORUS (P) 0.010 0.015
 TOTAL ORTHOPHOSPHATE (P) 0.002 0.002
 SPECIFIC CONDUCTANCE (MICROMHOS) 60 60
 WATER TEMPERATURE (DEG C) 18.7 18.3
 COLOR (PLATINUM-COBALT UNITS) 20 25
 SECCHI-DISC VISIBILITY (FT) 8
 DISSOLVED OXYGEN 9.0 9.2

LAKE SHORELINE COVERED BY EMERSED PLANTS 76-100 %
 LAKE SURFACE COVERED BY EMERSED PLANTS 26- 50 %

DATE 8/21/74
 TIME 1415
 NUMBER OF FECAL COLIFORM SAMPLES 3
 FECAL COLIFORM, MINIMUM (COL./100ML) <1
 FECAL COLIFORM, MAXIMUM (COL./100ML) 1
 FECAL COLIFORM, MEAN (COL./100ML) 1

REMARKS

 A SHALLOW LAKE CHOKED WITH EMERSED AND SUBMERSED AQUATIC VEGETATION.
 MOST OF THE LAKE BOTTOM WAS COVERED WITH EMERSED PLANTS (PONDWEED). THE
 LITTORAL BOTTOM IS MUCK AND LITTERED WITH LOGS AND WOOD DEBRIS.



N



0 1000 2000 FEET



EXPLANATION

— 10 —

Line of equal
water depth
Interval 5 feet

Price Lake, Mason County. From Washington
Department of Game, July 24, 1959.



Price Lake, Mason County. August 25, 1972. Approx. scale 1:12,000.

PRICKETT LAKE

MASON COUNTY

LATITUDE 47°22'35" LONGITUDE 122°53'29" T22N-R2W-23
PUGET SOUND BASIN

PHYSICAL DATA

DRAINAGE AREA 0.39 SQ MI
ALTITUDE 301. FT
LAKE AREA 74. ACRES
LAKE VOLUME 990. ACRE-FT
MEAN DEPTH 13. FT
MAXIMUM DEPTH 30. FT
SHORELINE LENGTH 1.7 MI
SHORELINE CONFIGURATION 1.4
DEVELOPMENT OF VOLUME 0.45
BOTTOM SLOPE 1.5 %
BASIN GEOLOGY SED./META.
INFLOW NONE VISIBLE
OUTFLOW CHANNEL PRESENT

CULTURAL DATA

RESIDENTIAL DEVELOPMENT 35 %
NUMBER OF NEARSHORE HOMES 41
LAND USE IN DRAINAGE BASIN
RESIDENTIAL URBAN 0 %
RESIDENTIAL SUBURBAN 11 %
AGRICULTURAL 3 %
FOREST OR UNPRODUCTIVE 56 %
LAKE SURFACE 30 %
PUBLIC BOAT ACCESS TO LAKE YES

WATER-QUALITY DATA (IN MG/L UNLESS OTHERWISE INDICATED)

SAMPLE SITE


DATE 8/27/74
TIME 1230 1235
DEPTH (FT) 3. 20.
TOTAL NITRATE (N) 0.00 0.00
TOTAL NITRITE (N) 0.00 0.00
TOTAL AMMONIA (N) 0.07 0.05
TOTAL ORGANIC NITROGEN (N) 0.36 0.43
TOTAL PHOSPHORUS (P) 0.009 0.018
TOTAL ORTHOPHOSPHATE (P) 0.005 0.004
SPECIFIC CONDUCTANCE (MICROMHOS) 14 14
WATER TEMPERATURE (DEG C) 22.0 20.5
COLOR (PLATINUM-COBALT UNITS) 5 10
SECCHI-DISC VISIBILITY (FT) 12
DISSOLVED OXYGEN 8.4 8.2

LAKE SHORELINE COVERED BY EMERSED PLANTS 26- 50 %
LAKE SURFACE COVERED BY EMERSED PLANTS NONE OR <1 %


DATE 8/27/74
TIME 1300
NUMBER OF FECAL COLIFORM SAMPLES 4
FECAL COLIFORM, MINIMUM (COL./100ML) <1
FECAL COLIFORM, MAXIMUM (COL./100ML) 8
FECAL COLIFORM, MEAN (COL./100ML) 3

REMARKS

CHANNELS HAVE BEEN DREDGED NEAR THE SOUTH AND NORTHWEST ENDS OF THE LAKE.
THE LITTORAL BOTTOM IS MUCK AND THE NEARSHORE BEACH IS GRAVEL. THE DO
WAS NEAR SATURATION THROUGHOUT THE WATER COLUMN.



Prickett Lake, Mason County. From Washington
Department of Fisheries, June 6, 1957.



Prickett Lake, Mason County. May 12, 1972. Approx. scale 1:12,000.

SIMPSON LAKE

MASON COUNTY

LATITUDE 47° 7'52" LONGITUDE 123°20'26" T19N-R5W-17
CHEHALIS RIVER BASIN

PHYSICAL DATA

DRAINAGE AREA 0.68 SQ MI
ALTITUDE 330. FT
LAKE AREA 29. ACRES
LAKE VOLUME 310. ACRE-FT
MEAN DEPTH 11. FT
MAXIMUM DEPTH 17. FT
SHORELINE LENGTH 0.90 MI
SHORELINE CONFIGURATION 1.2
DEVELOPMENT OF VOLUME 0.63
BOTTOM SLOPE 1.3 %
BASIN GEOLOGY SED./META.
INFLOW INTERMITTENT
OUTFLOW CHANNEL PRESENT

CULTURAL DATA

RESIDENTIAL DEVELOPMENT 3 %
NUMBER OF NEARSHORE HOMES 2
LAND USE IN DRAINAGE BASIN
RESIDENTIAL URBAN 0 %
RESIDENTIAL SUBURBAN 2 %
AGRICULTURAL 0 %
FOREST OR UNPRODUCTIVE 91 %
LAKE SURFACE 7 %
PUBLIC BOAT ACCESS TO LAKE --

WATER-QUALITY DATA (IN MG/L UNLESS OTHERWISE INDICATED)


SAMPLE SITE 1
DATE 8/15/74
TIME 1330 1335
DEPTH (FT) 3. 10.
TOTAL NITRATE (N) 0.01 0.02
TOTAL NITRITE (N) 0.00 0.00
TOTAL AMMONIA (N) 0.08 0.08
TOTAL ORGANIC NITROGEN (N) 0.44 0.37
TOTAL PHOSPHORUS (P) 0.011 0.014
TOTAL ORTHOPHOSPHATE (P) 0.002 0.002
SPECIFIC CONDUCTANCE (MICROMHOS) 50 50
WATER TEMPERATURE (DEG C) 19.9 19.1
COLOR (PLATINUM-COBALT UNITS) 15 15
SECCHI-DISC VISIBILITY (FT) >14
DISSOLVED OXYGEN 8.4 8.4

LAKE SHORELINE COVERED BY EMERSED PLANTS 51- 75 %
LAKE SURFACE COVERED BY EMERSED PLANTS NONE OR <1 %

DATE 8/15/74
TIME 1340
NUMBER OF FECAL COLIFORM SAMPLES 3
FECAL COLIFORM, MINIMUM (COL./100ML) <1
FECAL COLIFORM, MAXIMUM (COL./100ML) 1
FECAL COLIFORM, MEAN (COL./100ML) <1

REMARKS

AN EXTENSIVE NETWORK OF CHANNELS HAS BEEN DREDGED TO INCREASE WATERFRONT TO A PROPOSED RESIDENTIAL DEVELOPMENT. SUBMERSED PLANTS WERE THINLY SCATTERED AND PATCHY NEAR THE SHORELINE, BUT A HEAVY GROWTH OF SUBMERSED PLANTS (WATER MILFOIL) COVERED THE LAKE BOTTOM. THE LITTORAL BOTTOM IS MUCK.



N



0 500 1000 FEET

EXPLANATION

— 10 —

Line of equal
water depth
Interval 5 feet

Simpson Lake, Mason County. From Washington
Department of Game, June 1, 1946.



Simpson Lake, Mason County. June 30, 1974. Approx. scale 1:4800.

SPENCER LAKE

MASON COUNTY

LATITUDE 41°75'33" LONGITUDE 122°58'11" T21N-R2W-32
 PUGET SOUND BASIN

PHYSICAL DATA

 DRAINAGE AREA 1.68 SQ MI
 ALTITUDE 170. FT
 LAKE AREA 230. ACRES
 LAKE VOLUME 5200. ACRE-FT
 MEAN DEPTH 22. FT
 MAXIMUM DEPTH 36. FT
 SHORELINE LENGTH 4.3 MI
 SHORELINE CONFIGURATION 2.0
 DEVELOPMENT OF VOLUME 0.62
 BOTTOM SLOPE 1.0 %
 BASIN GEOLOGY SED./META.
 INFLOW NONE VISIBLF
 OUTFLOW CHANNEL PRESENT

CULTURAL DATA

 RESIDENTIAL DEVELOPMENT 33 %
 NUMBER OF NEARSHORE HOMES 89
 LAND USE IN DRAINAGE BASIN
 RESIDENTIAL URBAN 0 %
 RESIDENTIAL SUBURBAN 4 %
 AGRICULTURAL 3 %
 FOREST OR UNPRODUCTIVE 72 %
 LAKE SURFACE 21 %
 PUBLIC BOAT ACCESS TO LAKE YES

WATER-QUALITY DATA (IN MG/L UNLESS OTHERWISE INDICATED)

SAMPLE SITE


 DATE 1
 8/20/74
 TIME 1440 1445
 DEPTH (FT) 3. 26.
 TOTAL NITRATE (N) 0.00 0.00
 TOTAL NITRITE (N) 0.01 0.01
 TOTAL AMMONIA (N) 0.06 0.06
 TOTAL ORGANIC NITROGEN (N) 0.77 0.43
 TOTAL PHOSPHORUS (P) 0.009 0.018
 TOTAL ORTHOPHOSPHATE (P) 0.003 0.004
 SPECIFIC CONDUCTANCE (MICROMHOS) 30 30
 WATER TEMPERATURE (DEG C) 19.6 16.3
 COLOR (PLATINUM-CORALT UNITS) 0 0
 SECCHI-DISC VISIBILITY (FT) 10
 DISSOLVED OXYGEN 9.0 0.5

LAKE SHORELINE COVERED BY EMERSED PLANTS 51- 75 %
 LAKE SURFACE COVERED BY EMERSED PLANTS 1- 10 %


DATE 8/20/74
 TIME 1500
 NUMBER OF FECAL COLIFORM SAMPLES 4
 FECAL COLIFORM, MINIMUM (COL./100ML) <1
 FECAL COLIFORM, MAXIMUM (COL./100ML) 20
 FECAL COLIFORM, MEAN (COL./100ML) 8

REMARKS

 DENSE BEDS OF EMERSED PLANTS WERE OBSERVED IN THE SHALLOW NORTH BAY AND
 THE SOUTHWEST BAY NEAR THE OUTLET.



Spencer Lake, Mason County. From Washington
Department of Game, July 30, 1947.



Spencer Lake, Mason County. May 12, 1972. Approx. scale 1:12,000.

STUMP LAKE

MASON COUNTY

LATITUDE 47° 6' 4" LONGITUDE 123°19'33" T19N-R5W-28

CHEHALIS RIVER BASIN

PHYSICAL DATA

DRAINAGE AREA	19.8 SQ MI
ALTITUDE	300. FT
LAKE AREA	29. ACRES
LAKE VOLUME	260. ACRE-FT
MEAN DEPTH	9. FT
MAXIMUM DEPTH	21. FT
SHORELINE LENGTH	1.5 MI
SHORELINE CONFIGURATION	2.0
DEVELOPMENT OF VOLUME	0.44
BOTTOM SLOPE	1.7 %
Basin Geology	IGNEOUS
INFLOW	PERENNIAL
OUTFLOW CHANNEL	ABSENT

CULTURAL DATA

RESIDENTIAL DEVELOPMENT	0 %
NUMBER OF NEARSHORE HOMES	0
LAND USE IN DRAINAGE BASIN	
RESIDENTIAL URBAN	0 %
RESIDENTIAL SUBURBAN	<1 %
AGRICULTURAL	<1 %
FOREST OR UNPRODUCTIVE	99 %
LAKE SURFACE	1 %
PUBLIC BOAT ACCESS TO LAKE	YES

WATER-QUALITY DATA (IN MG/L UNLESS OTHERWISE INDICATED)


SAMPLE SITE	1
DATE	8/15/74
TIME	1420 1425
DEPTH (FT)	3. 16.
TOTAL NITRATE (N)	0.02 0.00
TOTAL NITRITE (N)	0.00 0.01
TOTAL AMMONIA (N)	0.09 2.0
TOTAL ORGANIC NITROGEN (N)	0.64 0.40
TOTAL PHOSPHORUS (P)	0.041 0.091
TOTAL ORTHOPHOSPHATE (P)	0.008 0.66
SPECIFIC CONDUCTANCE (MICROMHOS)	66 110
WATER TEMPERATURE (DEG C)	19.3 11.1
COLOR (PLATINUM-CORALT UNITS)	10 75
SECCHI-DISC VISIRILITY (FT)	8
DISSOLVED OXYGEN	9.7 0.2

LAKE SHORELINE COVERED BY EMERSED PLANTS	26- 50 %
LAKE SURFACE COVERED BY EMERSED PLANTS	1- 10 %

DATE	8/15/74
TIME	1440
NUMBER OF FECAL COLIFORM SAMPLES	3
FECAL COLIFORM, MINIMUM (COL./100ML)	<1
FECAL COLIFORM, MAXIMUM (COL./100ML)	1
FECAL COLIFORM, MEAN (COL./100ML)	1

REMARKS

THE LAKE IS AN OLD CREEK CHANNEL FILLED WITH STUMPS AND DEBRIS. TREES OVERHANG THE WATER AT THE SHORELINE. SUBMERSED PLANTS COVERED MOST OF THE LAKE BOTTOM, WHICH IS SOFT MUCK. AN ALGAL BLOOM WAS OBSERVED.



Stump Lake, Mason County. From
U.S. Geological Survey, May 29, 1974.



Stump Lake, Mason County. August 25, 1972. Approx. scale 1:12,000.

TEE LAKE

MASON COUNTY

LATITUDE 47°25'46" LONGITUDE 123° 1'24" T22N-R3W-2
PUGET SOUND BASIN

PHYSICAL DATA

DRAINAGE AREA 0.97 SQ MI
ALTITUDE 390. FT
LAKE AREA 47. ACRES
LAKE VOLUME 420. ACRE-FT
MEAN DEPTH 9. FT
MAXIMUM DEPTH 17. FT
SHORELINE LENGTH 1.7 MI
SHORELINE CONFIGURATION 1.8
DEVELOPMENT OF VOLUME 0.52
BOTTOM SLOPE 1.0 %
BASIN GEOLOGY SED./META.
INFLOW NONE VISIBLE
OUTFLOW CHANNEL PRESENT

CULTURAL DATA

RESIDENTIAL DEVELOPMENT 28 %
NUMBER OF NEARSHORE HOMES 23
LAND USE IN DRAINAGE BASIN
RESIDENTIAL URBAN 0 %
RESIDENTIAL SUBURBAN 3 %
AGRICULTURAL 0 %
FOREST OR UNPRODUCTIVE 89 %
LAKE SURFACE 8 %
PUBLIC BOAT ACCESS TO LAKE YES

WATER-QUALITY DATA (IN MG/L UNLESS OTHERWISE INDICATED)


SAMPLE SITE 1
DATE 8/26/74
TIME 1230 1235
DEPTH (FT) 3. 13.
TOTAL NITRATE (N) 0.02 0.02
TOTAL NITRITE (N) 0.00 0.01
TOTAL AMMONIA (N) 0.05 0.09
TOTAL ORGANIC NITROGEN (N) 0.24 0.25
TOTAL PHOSPHORUS (P) 0.010 0.014
TOTAL ORTHOPHOSPHATE (P) 0.005 0.005
SPECIFIC CONDUCTANCE (MICROMHOS) 21 21
WATER TEMPERATURE (DEG C) 21.5 20.2
COLOR (PLATINUM-COBALT UNITS) 0 0
SECCHI-DISC VISIBILITY (FT) 8
DISSOLVED OXYGEN 9.0 8.0

LAKE SHORELINE COVERED BY EMERSED PLANTS 51- 75 %
LAKE SURFACE COVERED BY EMERSED PLANTS 11- 25 %

DATE 8/26/74
TIME 1230
NUMBER OF FECAL COLIFORM SAMPLES 3
FECAL COLIFORM, MINIMUM (COL./100ML) <1
FECAL COLIFORM, MAXIMUM (COL./100ML) <1
FECAL COLIFORM, MEAN (COL./100ML) <1

REMARKS

EMERSED PLANTS WERE SCATTERED IN PATCHES ALONG THE SHORELINE AND IN DENSE BEDS IN THE BAY AREAS. SUBMERSED PLANTS (PONDWEED) COVERED A LARGE PERCENTAGE OF THE LAKE BOTTOM. FLOATING LOGS AND WOOD DEBRIS COVERED THE SHORELINE LOCALLY. THE LITTORAL BOTTOM IN THE BAY AREAS IS MOSTLY MUCK.



N




0 500 1000 FEET

EXPLANATION

—10—

Line of equal
water depth
Interval 5 feet

Tee Lake, Mason County. From Washington
Department of Game, June 12, 1950.



Tee Lake, Mason County. May 12, 1972. Approx. scale 1:12,000.

TIGER LAKE

MASON COUNTY

LATITUDE 47°30'31" LONGITUDE 122°50' 8" T23N-R1W-5
 PUGET SOUND BASIN

PHYSICAL DATA

 DRAINAGE AREA 0.70 SQ MI
 ALTITUDE 496. FT
 LAKE AREA 110. ACRES
 LAKE VOLUME 2100. ACRE-FT
 MEAN DEPTH 19. FT
 MAXIMUM DEPTH 40. FT
 SHORELINE LENGTH 2.5 MI
 SHORELINE CONFIGURATION 1.7
 DEVELOPMENT OF VOLUME 0.48
 BOTTOM SLOPE 1.6 %
 BASIN GEOLOGY SED./META.
 INFLOW INTERMITTENT
 OUTFLOW CHANNEL PRESENT

CULTURAL DATA

 RESIDENTIAL DEVELOPMENT 100 %
 NUMBER OF NEARSHORE HOMES 80
 LAND USE IN DRAINAGE BASIN
 RESIDENTIAL URBAN 0 %
 RESIDENTIAL SUBURBAN 14 %
 AGRICULTURAL 0 %
 FOREST OR UNPRODUCTIVE 61 %
 LAKE SURFACE 25 %
 PUBLIC BOAT ACCESS TO LAKE YES

WATER-QUALITY DATA (IN MG/L UNLESS OTHERWISE INDICATED)

SAMPLE SITE


 DATE 6/73/20
 TIME 950 - 1000
 DEPTH (FT) 3. 33.
 TOTAL NITRATE (N) 0.01 0.01
 TOTAL NITRITE (N) 0.00 0.00
 TOTAL AMMONIA (N) 0.03 0.07
 TOTAL ORGANIC NITROGEN (N) 0.07 0.06
 TOTAL PHOSPHORUS (P) 0.004 0.061
 TOTAL ORTHOPHOSPHATE (P) 0.001 0.002
 SPECIFIC CONDUCTANCE (MICROMHOS) -- --
 WATER TEMPERATURE (DEG C) 17.8 15.5
 COLOR (PLATINUM-COBALT UNITS) 0 5
 SECCHI-DISC VISIBILITY (FT) 12
 DISSOLVED OXYGEN 9.2 5.7

LAKE SHORELINE COVERED BY EMERSED PLANTS 11- 25 %
 LAKE SURFACE COVERED BY EMERSED PLANTS NONE OR <1 %

DATE 6/20/73
 TIME 1035
 NUMBER OF FECAL COLIFORM SAMPLES 4
 FECAL COLIFORM, MINIMUM (COL./100ML) <1
 FECAL COLIFORM, MAXIMUM (COL./100ML) 30
 FECAL COLIFORM, MEAN (COL./100ML) 10

REMARKS

 THE LITTORAL BOTTOM OF GRAVEL, COBBLE, AND SAND SUPPORTED A SPARSE GROWTH OF AQUATIC MACROPHYTES. IN 1973 THE U.S. GEOLOGICAL SURVEY SAMPLED THE LAKE FOUR TIMES. THE PLANT SURVEY WAS MADE ON AUGUST 14, 1973.



Tiger Lake, Mason County. From Washington
Department of Game, June 18, 1952.



Tiger Lake, Mason County. May 28, 1972. Approx. scale 1:12,000.

TIMBER LAKE

MASON COUNTY

LATITUDE 47°13'26" LONGITUDE 122°58'48" T20N-R2W-18
 PUGET SOUND BASIN

PHYSICAL DATA

 DRAINAGE AREA 1.82 SQ MI
 ALTITUDE 180. FT
 LAKE AREA 82. ACRES
 LAKE VOLUME 780. ACRE-FT
 MEAN DEPTH 10. FT
 MAXIMUM DEPTH 21. FT
 SHORELINE LENGTH 2.8 MI
 SHORELINE CONFIGURATION 2.2
 DEVELOPMENT OF VOLUME 0.46
 BOTTOM SLOPE 0.99 %
 BASIN GEOLOGY SED./META.
 INFLOW INTERMITTENT
 OUTFLOW CHANNEL PRESENT

CULTURAL DATA

 RESIDENTIAL DEVELOPMENT 31 %
 NUMBER OF NEARSHORE HOMES 17
 LAND USE IN DRAINAGE BASIN
 RESIDENTIAL URBAN 0 %
 RESIDENTIAL SUBURBAN 10 %
 AGRICULTURAL 0 %
 FOREST OR UNPRODUCTIVE 83 %
 LAKE SURFACE 7 %
 PUBLIC BOAT ACCESS TO LAKE --

WATER-QUALITY DATA (IN MG/L UNLESS OTHERWISE INDICATED)

SAMPLE SITE


 DATE 1
 8/20/74
 TIME 1320 1325
 DEPTH (FT) 3. 11.
 TOTAL NITRATE (N) 0.01 0.00
 TOTAL NITRITE (N) 0.01 0.01
 TOTAL AMMONIA (N) 0.08 0.07
 TOTAL ORGANIC NITROGEN (N) 0.37 0.44
 TOTAL PHOSPHORUS (P) 0.014 0.011
 TOTAL ORTHOPHOSPHATE (P) 0.006 0.004
 SPECIFIC CONDUCTANCE (MICROMHOS) 40 40
 WATER TEMPERATURE (DEG C) 19.6 19.0
 COLOR (PLATINUM-COBALT UNITS) 30 30
 SECCHI-DISC VISIBILITY (FT) 5
 DISSOLVED OXYGEN 8.3 8.0

LAKE SHORELINE COVERED BY EMERSED PLANTS 11- 25 %
 LAKE SURFACE COVERED BY EMERSED PLANTS NONE OR <1 %

DATE 8/20/74
 TIME 1340
 NUMBER OF FECAL COLIFORM SAMPLES 4
 FECAL COLIFORM, MINIMUM (COL./100ML) <1
 FECAL COLIFORM, MAXIMUM (COL./100ML) 13
 FECAL COLIFORM, MEAN (COL./100ML) 6

REMARKS

 A RECENT ARTIFICIAL LAKE CREATED BY DREDGING THE SWAMPY LAND AND DAMMING THE OUTLET CREEK. THE LAKE IS FED BY PHILLIPS LAKE VIA A LARGE MARSH. A DENSE COVER OF SUBMERSED PLANTS (ELODEA) WAS OBSERVED LOCALLY IN THE LAKE.



Timber Lake, Mason County. From
U.S. Geological Survey, December 27, 1973.



Timber Lake, Mason County. September 2, 1973. Approx. scale 1:12,000.

WOOTEN LAKE

MASON COUNTY

LATITUDE 47°27'55" LONGITUDE 122°58'57" T23N-R2W-19
TAHUYA RIVER BASIN

PHYSICAL DATA

DRAINAGE AREA 0.32 SQ MI
ALTITUDE 407. FT
LAKE AREA 68. ACRES
LAKE VOLUME 1500. ACRE-FT.
MEAN DEPTH 23. FT
MAXIMUM DEPTH 36. FT
SHORELINE LENGTH 1.5 MI
SHORELINE CONFIGURATION 1.3
DEVELOPMENT OF VOLUME 0.63
BOTTOM SLOPE 1.8 %
BASIN GEOLOGY SED./META.
INFLOW NONE VISIBLE
OUTFLOW CHANNEL PRESENT

CULTURAL DATA

RESIDENTIAL DEVELOPMENT 58 %
NUMBER OF NEARSHORE HOMES 47
LAND USE IN DRAINAGE BASIN
RESIDENTIAL URBAN 0 %
RESIDENTIAL SUBURBAN 19 %
AGRICULTURAL 0 %
FOREST OR UNPRODUCTIVE 48 %
LAKE SURFACE 33 %
PUBLIC BOAT ACCESS TO LAKE YES

WATER-QUALITY DATA (IN MG/L UNLESS OTHERWISE INDICATED)



SAMPLE SITE 1
DATE 8/22/74
TIME 1145 1150
DEPTH (FT) 3. 23.
TOTAL NITRATE (N) 0.01 0.01
TOTAL NITRITE (N) 0.00 0.00
TOTAL AMMONIA (N) 0.04 0.08
TOTAL ORGANIC NITROGEN (N) 0.36 0.26
TOTAL PHOSPHORUS (P) 0.005 0.005
TOTAL ORTHOPHOSPHATE (P) 0.002 0.002
SPECIFIC CONDUCTANCE (MICROMHOS) 30 25
WATER TEMPERATURE (DEG C) 21.0 20.0
COLOR (PLATINUM-COBALT UNITS) 15 10
SECCHI-DISC VISIBILITY (FT) 15
DISSOLVED OXYGEN 8.8 8.4

LAKE SHORELINE COVERED BY EMERSED PLANTS 11- 25 %
LAKE SURFACE COVERED BY EMERSED PLANTS NONE OR <1 %

DATE 8/22/74
TIME 1200
NUMBER OF FECAL COLIFORM SAMPLES 3
FECAL COLIFORM, MINIMUM (COL./100ML) <1
FECAL COLIFORM, MAXIMUM (COL./100ML) 6
FECAL COLIFORM, MEAN (COL./100ML) 2


REMARKS

THE LAKE DRAINS TO HAVEN LAKE. THE SHORES ARE GRAVEL AND SUPPORTED ONLY THINLY SCATTERED EMERSED PLANTS. THE DO WAS NEAR SATURATION THROUGHOUT THE ENTIRE WATER COLUMN.



EXPLANATION
 — 20 —
 Line of equal
 water depth
 Interval 10 feet

Wooten Lake, Mason County. From Washington
 Department of Game, July 23, 1948.



Wooten Lake, Mason County. August 24, 1972. Approx. scale 1:12,000.